No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
18	Chunam plastering smooth	Sqr.	3 0 0	50·00	150
19	White and colour washing	,,	0 5 0	50·00	16
20(*a*)	Painting with two coats of chocolate paint	,,	2 13 0	5·51	16
(*b*)	Do with Lac Factory green			5·51	
21	Roofing with trafford sheets on angle iron purlins over existing roof frame including fixing with bolts, nuts, etc., complete	,,	39 0 0	3·44	134
22	Flooring with 1½″ cement concrete over 3″ ordinary concrete of granite jelly ½″ cement plastering with red finish cutting borders and squares, etc., complete	,,	18 0 0	11·78	212
23	Cornice 9″ thick as per design	R.ft.	0 8 0	243	122
24	Building steps with earthwork foundation granite jelly concrete (brick in chunam masonry) and providing burnt stone slabs over and two lines dressing to slabs, etc., complete	No.	3 0 0	5	15

M. N. LAKSHMAN RAO,
Assistant Engineer.

HASSAN DIVISION.

Abstract Notification dated 26th October 1939.

The attention of the public is drawn to the tender notification in the *Mysore Gazette*, dated the 2nd November 1939, *vide* pages 2206-2207 of Part VI, calling for tenders for construction of a Combined Maternity and Child Welfare Centre at Konanur, Arkalgud Taluk, Hassan District, before Monday the 27th November 1939.

Notification dated 6th November 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 3 P.M., on Saturday the 2nd December 1939 for constructing Practical Hall and Lecture Hall in the rear of the Government High School by completing the quadrangle of the building at Hassan.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division, Hassan, and should be superscribed as "Tender for constructing Practical Hall and Lecture Hall in the rear of the Government High School by completing the quadrangle of the building at Hassan." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 1,000 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest). In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date of opening. The final acceptance of the tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer, in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Hassan Division, Hassan, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised, and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department for the current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member therefor or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Hassan Division, Hassan, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities as estimates are only approximate and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer, or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department by the end of May 1940, failing which, the Executive Engineer may, at his discretion, levy a penalty up to Rs. 500 which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Superintending Engineer, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Hassan Division, Hassan.

19. No claims for damages for delays caused by officers of the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will however, be considered on the merits of each case.

20. The contract should not be sublet.

21. Copies of tenders in the prescribed form are available in the Office of the Executive Engineer, Hassan Division, only on payment of annas four.

22. Amount of estimate is Rs. 12,000.

23. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer, and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

24. The contractors should arrange for the payment of royalty and tolls.

Estimate for constructing Practical Hall and Lecture Hall in the rear of the Government High School by completing the Quadrangle of the building at Hassan.

Sl. No.	Details of work	Per	Rate	Quantity
			Rs. a. p.	
1	Earthwork excavation for foundation and filling in basement	C.yd.	0 3 6	153
2	Stone jelly concrete in lime mortar	C.ft.	0 4 6	1,192
3	Size stone in mortar foundation with necessary bond slabs at every 6 ft. apart, including basement	,,	0 5 0	3,759
4	Burnt brick in mortar for superstructure with bond slabs	,,	0 4 6	5,012
5	Burnt stone slabs 6″ thick dressed and fixed in mortar	S.ft.	0 8 0	1,034½
6	Cut stone pillars 7 ft. high with ornamental capital with dressing including fixing	Each	25 0 0	10
7	Rolled steel beams for side halls	Cwt.	15 0 0	71·51
8	Teakwood wrought and put up with wood oiling, etc., complete	C.ft.	4 12 0	303·50
9	Teakwood windows wrought and put up with 3″×4″ frames and 1¼″ thick panelled shutters outside and glazed shutters inside with ¾″ iron bars, hinges, etc., complete	S.ft.	2 0 0	542
10	Teakwood doors wrought and put up with 3″×4″ frames and 1¼″ thick panelled shutters with necessary iron fittings, etc., complete	,,	1 8 0	272

Sl. No.	Details of work	Per	Rate	Quantity
			Rs. a. p.	
11	Providing and fixing R. C. ventilators	S.ft.	1 2 0	176
12	Roofing with Madras Terrace with a chamber of 1 in 40, bottom course laid with burnt brick on edge and on the top 3″ thick lime concrete with burnt brick jelly well beaten and on top 3 courses of flat tiles laid diagonally and bottom and top plastered smoothly	Sqr.	35 0 0	28·91
13	Parapet wall—burnt brick in mortar 9″ thick 1½ ft. high including blocking course 6″ high and coping and plastering, etc., complete	R.ft.	1 0 0	342¾
14	Brick in mortar cornice 9″ thick	,,	0 10 0	347
15	Roofing with first class Mangalore tiles on teakwood reepers	Sqr.	24 0 0	5·61
16	Chunam plastering and rounding of corners	,,	3 8 0	105·93
17	White and colour washing as per plastering above	,,	0 4 6	108·00
18	Painting doors and windows with grey colour 2 coats	,,	3 8 0	23·10
19	Mortar bands over roof	R.ft.	0 2 0	48
20	Flooring with 3″ lime concrete and 1½″ cement in stone jelly including plastering and cutting tiles, etc., complete	Sqr.	20 0 0	25·07
21	Cement pointing to basement	,,	3 8 0	5·45
22	Providing zinc sheet for valleys including teakwood planking ½″ thick 3 ft. wide with necessary plastering and wood-oiling, etc.	R.ft.	2 4 0	26
23	Teakwood eave boards plain 9″ thick with wood oiling or chocolate painting	,,	0 8 0	54
24	Constructing exmet wall in burnt brick in composite mortar and exmet at every 3 courses including plastering, etc., complete	S.ft.	0 8 0	108
25	Boxing girders with cement concrete	R.ft.	0 10 0	214
26	Earthwork filling up the quadrangle	C.yd.	0 3 0	500
27	Providing and fixing rectangular cast iron rain water pipes with necessary bends, heads, etc., complete embedded in masonry	R.ft.	1 8 0	208
28	Removing and refixing burnt stone slabs in mortar in the quadrangle	S.ft.	0 2 0	120

Notification dated 7th November 1939.

Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 4th December 1939 till 3 P.M., for Improving the Adikarnataka Boarding Institute at Hassan.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division, Hassan, and should be superscribed as "Tender for Improving the Adikarnataka Boarding Institute at Hassan." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 250 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest). In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department.

4. The tenders will be opened in the presence of such of the tenderers who wish to be present on the date of opening. The final acceptance of the tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Hassan Division, Hassan, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the P. W. D. Current Schedule of Rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Hassan Division, Hassan, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the P. W. D. by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty up to Rs. 500 which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Hassan Division, Hassan.

19. No claims for damages for delays caused by officers of the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the Departmental Officers will be, however, considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

23. Copies of tender in the prescribed form are available from the Office of the Executive Engineer only on a payment of Re. 0-4-0 per form.

Abstract estimate for improving the Adikarnataka Boarding Institute at Hassan.

No.	Items of work	Unit	Quantity	Rate	Cost
				Rs. a. p.	Rs.
1	Earthwork excavation for foundations	C.yd.	237	0 3 0	
2	Stone jelly concrete in lime mortar	C.ft.	757	0 4 0	
3	Size stone in clay	,,	2,095	0 3 6	
4	Burnt stone slabs 6" thick, dressed and fixed	S.ft.	373	0 8 0	
5	Burnt stone slabs 4" thick, dressed and fixed	,,	197	0 6 0	
6	Constructing burnt brick in clay	C.ft.	3,278	0 3 0	
7	Plastering with lime mortar	Sqr.	54·66	3 8 0	
8	Stucco plastering	,,	12·80	4 0 0	
9	Chunam pattis around windows	,,	2·52	8 0 0	
10	Creosoted wood wrought and put up	C.ft.	285·39	2 12 0	
11	Roofing with 1st Class Mangalore tiles over Nandy rec-pers	Sqr.	34·37	21 0 0	
12	Ridge tiles set in mortar and pointed with cement	R.ft.	115	0 7 0	
13	Providing valley with planks and G. I. sheet and cement plastering ½" thick, complete 3' wide	,,	48	1 12 0	
14	Teakwood battened doors with 1¼" planks, bolts, padlocks, etc., complete	S.ft.	207	1 6 0	
15	Teakwood windows with battened shutters, hinges, iron bars, bolts, etc., complete	,,	80	1 12 0	
16	Teakwood glazed ventilators	,,	54	1 4 0	
17	Expanded metal partition with teakwood frame work as per existing pattern	,,	157	0 10 0	
18	Dismantling old work and removing debris	L. S.	..	15 0 0	
19	Flooring with 3" lime concrete and 1½" cement concrete and ½" thick cement plaster, complete	Sqr.	20·66	21 0 0	
20	Fixing old G. I. sheets for fuel shed with new washers and bolts, complete	,,	9·64	2 8 0	

No.	Items of work	Unit	Quantity	Rate	Cost
				Rs. a. p.	
21	Providing and fixing on G. I. sheets door with old G. I. sheet and new creosoted wood frame work, bolts, pad locks, etc., complete	S.ft.	60	0 4 0	
22	Providing and fixing 9" wide teakwood ornamental eave board as per existing pattern	R.ft.	226	0 9 0	
23	Painting wood work with chocolate paint of 2 coats	Sqr.	10·82	3 0 0	
24	White wash 2 coats	"	72·28	0 4 0	
25	Pointing with cement mortar	"	6 26	4 0 0	

P. SUBBA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 3rd November 1939.

The attention of the public is drawn to the Notification, advertised in the *Mysore Gazette*, dated 9th November 1939, Part VI, on pages 2256-2258 for 'constructing a lock-up building at Sagar Town, Shimoga District.'

The last date of receiving tender is 27th of November 1939.

Notification dated 9th November 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 4 P.M. on 11th December 1939, for repairing Sree Aswathanarayana Swamy Temple at Mahishi, Tirthahalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for repairing Sri Aswathanarayana Swamy Temple at Mahishi, Tirthahalli Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words, as well as in figures and they must be in specific terms of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. The successful candidate will be required to deposit another sum of Rs. 150 towards security deposit. This will be deducted from Bills.